

Ω OMEGAATM CONSTRUCTION



OUR SERVICES


- Construction
- Interior Design
- 3D Visualization
- SketchUp 3D Modeling
- Architectural Planning
- Renovation

CONTACT :  +91 9500955010  +91 9123579767

WE ARE SPECIALIZED IN




**COST EFFECTIVE
CONSTRUCTION**



**INNOVATIVE
CONSTRUCTION**



**PROFESSTIONAL
WORKMANSHIP**



**PREMIUM QUALITY
CONSTRUCTION**



**YOUR TRUST, OUR
FOUNDATION**

WE BUILD YOUR DREAM HOUSE

Imagine your dream home becoming a reality with our expert construction services!

Why Your Dream Home Matters

Your home is more than just a place to live; it's a sanctuary that reflects your lifestyle and aspirations. Let us help you create a space where memories are made and dreams thrive.



ARE YOU GOING TO
BUILD YOUR HOME OR
COMMERCIAL?

CONTACT US

A COMPANY WITH
30 YEARS OF EXCELLENCE
IN COMPLETING
BUILDINGS

FOLLOW US

 www.omegaconstruction.com

 OMEGAA CONSTRUCTION

 OMEGAA_CONSTRUCTION

 omegaasiva@gmail.com



OFFICE

No 3/28 Ellappa Nagar,
2nd Street, opposite collector
office, Kanchipuram,
Tamil Nadu - 631501

CONTACT US



+91 9500955010



+91 9123579767



OMEGAA CONSTRUCTION

KANCHIPURAM - +91 95009 55010/9123579767
CONSTRUCTION SPECIFICATION
ENGINEER: SIVAKUMAR V K

Date: DD/MM/YYYY

This Rate Valid From: DD/MM/YYYY To DD/MM/YYYY

Our Services & Materials

Rate per Sq.ft Rs. _____

S. No	DESCRIPTION	SPECIFICATION
1.	Rate For Construction	Rs. _____/sft
2.	Architectural 2D-Floor Plan	Yes
3.	Architectural 3D Elevation	No
4.	Sketchup 3D View	Yes
5.	3D Video Walk Around	No
6.	Structural Drawing All these drawings are Combined with Agreement or @ the previous stage of work	• Column • Footing • Plinth Beam • Lintel • Roof Beam • Roof Slab • Joinery Detail • Staircase Drawings
7.	MEP Drawing	Lighting and Fan Provision Drawing

8.	Work Update to Client	WhatsApp Photo/ Video Update
9.	Brand Change Assurance	99% Assured
10.	Construction Management	Direct Management
11	Column Structure	Yes
12.	Cement	CLASS- A - Ramco/Chettinad
13.	TMT- (ISI) STEEL	THIRUMALA JPR
14.	Paint Brand	Dulux / Asian
15.	M-Sand & P- Sand	M & P -Sand
16.	Concreting Method	With Vibrator machine if required
17.	Brick Work	Wire Cut Red Bricks

Foundation & Basement

18.	Foundation Depth from the Ground Level	6 Feet
19.	Footing Concrete	M-15 – 1:2:4
20.	Footing Concrete Depth	1'3" to 1'6"
21.	Minimum Size of Column Dimension & Size of Steel	Mim size: 9" X 9" & 4 No / 16# Stirrups 8#
22.	Plinth Beam Concrete	M-15 – 1:2:4
23.	Minimum Size of Rod in Beam	#10 mm/#12 mm / Stirrups at #8mm
24.	Column Shuttering	Metal Box
25.	Basement Height from Existing Ground Level	2' Height (Inc. Plinth Beam)
26.	Brick work @ Basement	Wire Cut Red Brick
27.	Basement Brick Work Plastering	All the Walls are Cement plastered out sides only.
28.	Basement PCC	PCC 1:4:8 Of 100mm thick
29.	Anti Termite Treatment	Yes, Treated at Basement
30.	Basement Filling	Gravel
31.	Basement height of parking floor	2' below ground FFL or Site condition

Super Structure

32.	External Wall Size	9" Thickness
33.	Internal Wall	4.5"/9" Thickness
34.	Parapet wall	3' height of 4.5" thick wall
35.	Roof Concrete - Grade	M-15 – (1:2:4)
36.	Other Concrete at Site (Column, Beam, Lintel etc.,)	M15 - (1:2:4)
37.	Sill Level Beam below Windows at 3'	2" thick Sill Concrete on outer walls using Readymade Sill Plate
38.	Reinforcement of Brick Work -4.5" Thick Wall	Below Sill Lvl-1Nos Above Sill Lvl-1Nos
39.	Lintel Beam at 7'	Full Lintel Above all walls.
40.	Sunshades - 2' width	No Extra Charges
41.	Cupboard in Bedroom (4' X 7') Loft One Side - 2' width	No Extra Charges C/B – (Cuddapha Slab)
42.	Cupboard in Bedroom (4' X 7') Loft in Kitchen - 2' Width	No Extra Charges C/B – (Cuddapha Slab)

43.	Hall	No Cupboards & Loft
44.	Roof Height	10'9" Ht Including Slab Thickness
45.	Ceiling Height	10'1" Ht
46.	Roof Slab Thickness	5" Thick (as per Structural Drawing)
47.	Staircase structure	RCC Waist slab and brick work

Curing Period for Civil Works

48.	Curing done	Two times curing done except on Sundays
49.	Roof concrete curing	15 Days
50.	Brick work Curing	8 Days
51.	Plastering Curing	8 Days
52.	DE shuttering of Roof Slab	15th Day

Tile & Granite

53.	Flooring Tile (Size- 2x2)	Rs.50/sft
54.	Toilet Tile	Rs.40.00 up to Lintel Level
55.	Kitchen Wall Tile	Rs.40.00 up to 2'from kitchen top
56.	Parking Floor Tile	Rs.40.00
57.	Main Door Entrance Step	Rs.40.00 with Anti-skid tiles
58.	Inner Staircase Step Tile	Rs.50.00/Sft
59.	Outer Staircase Step	Cement Flooring
60.	Kitchen Countertop	Granite Rs.120/Sft
61.	Floor Spacers Provided	For Toilet Floor Tiles
62.	Spacers (Provided for Building Flooring)	No

Doors and Windows: Joiners

63.	Main Door- (Provides one number only in a Plot (Size 3'6' x 7')	1.5" Thick-Teak Door & Frame Worth Rs.30000.00
64.	Main Door Fittings	Full Brass
65.	All Other Doors On Every Floor (Size 3' x 7')	Teak Frame & Laminate Door
66.	All Other Doors Fittings On Every Floor (Size 3' X 7')	SS or Brass Coated Fittings
67.	Toilet Door- (Size 2'6' x 7')	PVC Door
68.	Window Frame And Shutters	UPVC (white) Rs.500/sft / 2 nd Teak wood window with paint finish
69.	Window Grill	10mm Rod
70.	Window Glass	4mm Design Glass

Plumbing Works

71.	External Plumbing Pipe material:	PVC 15g (Finolex / Ashirvad)
72.	Internal Hot Cold Plumbing Pipe material	CPVC (Finolex / Ashirvad)
73.	Toilet - Water Heater Provision	Provided
74.	Corporation Water Inlet till Site Boundary	Provided
75.	Plumbing-Supply Inside Toilet	Bore Water
76.	Kitchen SS Sink & Taps	Provided
77.	One Wash Basin	Provided
78.	Plumbing Pipe - Vertical Lines Fixing	Fixing Along with Wall
79.	Sanitary Fittings	Parry ware - Basic model

Electrical

80.	Wire	Orbit
81.	DTH, Tv & Wi-Fi Cable Conduits	Provided
82.	Chemical Earthing	Additionally Charged
83.	AC Provision	Only In all Bedrooms
84.	Switches & Sockets (White Color)	Anchor (Rider)
85.	3 Phase Wiring (with in the building)	Provided
86.	UPS wiring	Provided at all Switch Box

87. Electrical Points & Switch Box on Room Wall

Rooms	Tube lights	Bulb	5/15 Socket with Control	Night Lamp	Fan	AC	Fridge / Mixier	TV	Gaiser
Hall	2	1	2 / 2	0	2	0	0	1	0
Bed Rooms	2	1	2 / 0	1	1	1	0	1	0
Kitchen	2	1	2 / 2	1	1	0	3	0	0
Bathrooms	0	1	0	0	0	0	0	0	1
Passage	1	1	1 / 0	0	0	0	0	0	0
Portico	2	1	1 / 1	0	1	0	0	0	0

Common Light – Provide Wherever necessary.

Plastering and Painting Works

88.	Ceiling Plastering	CM 1:4 Mix
89.	Internal Wall Plastering	CM 1:5 Mix
90.	External Wall Plastering	CM 1:5 Mix
91.	External Walls & Internal Ceiling Painting	1 white coat + 2 coats of Emulsion
92.	Internal Wall Putty	2 coat Putty + 1 coat wall Primer + 2 coats of Emulsion
93.	Polish work	Main door only
94.	Painting work	Door frame, windows and grill
95.	Toilet Water Proofing	Ultra Tech Water Proofing Component
96.	To Avoid Cracks	Pillars Brick, Beams Brick Joints, Electrical Groves provided with Glass fiber mesh

Other Works

97.	Inner, Outer & Balcony Railing	MS Railing
98.	Sunken slab for Toilet (If required)	No extra charges
99.	Column Concrete on Site Preparation	Manually
100.	MS Stand for Drying cloth in terrace	1 set provided
101.	Weathering Course	Morter with Baby chips & Cool Roof Tile
102.	Inspection Chambers	No extra Charges

Additional Works

103.	Washing Stone, Water Supply & Drainage	Additionally charged
104.	Soak Pit (If Drainage not Provided in Lay-Out)	Additionally charged
105.	Soil Test	Additionally charged as per Site Condition
106.	Water Sump wire cut red Brick work	Additionally charged
107.	RCC Tank (4" Block Work + 4" Concrete with 10 mm X 8 mm Single Mat)	Additionally charged
108.	Septic Tank Wire Cut Red Bricks	Additionally charged
109.	Tie Beam Basement Level	Additionally charged (if Basement is above 4'6")
110.	Over Head Tank Sintex / Brick Work / RCC with Brick work	Additionally charged
111.	Compound Wall: 4.5" Thick wire cut brick Wall up to 5' from Ground level	Additionally charged
112.	Ramp	Additionally Charged

113.	MS Gate of 11' Wide	Additionally Charged
114.	Planter Box Outside the Building (If required)	Additionally Charged
115.	Pergola in Concrete or Steel Fabrication (If required)	Additionally Charged
116.	Glass Works: Toughen Glass / Elevation Glass Works (If required)	Additionally Charged
117.	MS Steel Staircase to 2nd Floor (or) Head Room	Additionally charged
118.	Additional Back Area for Gravel Filling, PCC Flooring	Additionally charged
119.	Additional Ceiling Height (if required)	Additionally charged
120.	Additional Basement Height if required	Additionally charged
121.	Special Elevation Features or Masonry works outside Plinth Area attracts Cost	Additionally Charged
122.	Compound Wall Elevation Works	Additionally Charged
123.	Safety Grill Door	Additionally Charged
124.	Additional Loft Storage Above Pooja or Outer Toilet (if required)	Additionally Charged

125.	Toilet Nische (Shell)	Additionally Charged
126.	Over Cylinder Provision Outside Kitchen	Additionally Charged
127.	False Ceiling Works	Additionally Charged
128.	DTH, TV & Wi-Fi Cable Conduits	Additionally Charged
129.	Chemical Earthing	Additionally Charged
130.	Electric Vehicle Charging Provision	Additionally Charged
131.	Dishwasher	Additionally Charged
132.	Solar Provision in Terrace	Additionally Charged
133.	MCB Panel Box With 3 Phase Rotary with MCB	Additionally Charged
134.	CCTV Piping & Wiring Only	Additionally Charged
135.	Arch Doors and Windows	Additionally Charged
136.	Sloped Roofing with Roof Tiles	Additionally Charged
137.	All Type of Interior Works	Additionally Charged
138.	Additional Electrical Points if Required (Refer Item No 87.)	Additionally Charged

	NOTE: Owner's Scope
1	Electricity / EB Bill will be provided by Owner – 1/3 Phase
2	Water will be provided by Owner
3	Land for Workers' Shed will be provided by Owner
4	Building Plan approval
5	Borewell & Pump Set will be provided by Owner
6	Electricity Final Shifting 1/3 Phase Connection, DB Panel Box & Govt.Charges
7	Electrical fittings like Fan, Light, Ac, Motor Pumps, Pressure Pump Water, Heater will be provided and fitting charge paid by Owner
8	Interior Works, False ceiling are not included in the estimation

Statement of Area and Construction Cost _____ sq. ft. Built-up Area

S. No	Area Statement	In Sq. ft
1.	Ground Floor	_____
2.	First Floor	_____
3.	Second Floor / Headroom	_____
4.	Staircase & portico	_____

Cost Of Constructing _____ Sqft Of Built-up Area –

Area of Building in Sqft X Rate /Sqft = Total Cost Rs_____